

Dangisharan Rural Municipality.
Office of the Rural Municipal Executive.

Hekuli, Dang.
 Lumbini Province

BOO



Estimated Amount without VAT: _____

84.680.53

(Signature)
कृष्ण बहादुर नेपाली
 प्रमुख प्रशासकीय अधिकारी

Name of project :- Butaniya Dabri jame sadak Gravel yojana

Name Of the Place:- Dangisharan Ga.pa ward 7

Name Of the Work:- Graveling works

| S N | DESCRIPTION | UNIT | TOTAL QUANTITY | | Rate | AMOUNT | REMARKS |
|-------------------------|---|------|----------------|-------|------|--------|---------|
| | | | Fig | Words | | | |
| 1 | Providing and laying granular local mix gravel on prepared road surface by mechanical means all complete. | Cum. | 73.50 | | | | |
| SUB-Total Amount: | | | | | | | |
| Vat @ 13% | | | | | | | |
| Grand total amount (Rs) | | | | | | | |

Name of Contractor:- _____

Address:- _____

Date:- _____

Dangisharan Rural Municipality.
Office of the Rural Municipal Executive.

Hekuli, Dang.
Lumbini Province Nepal

योजना को नाम : सतिमन्दिर भसनेवा तटबन्द निर्माण योजना
ठेगाना :- दंगीशरण गाउँपालिका ४

Bill Of Quantities(BOQ)

Name Of the Place:- ward no. - 4 baibang

| SN | Discription | Unit | Quantity | Bidder's Rate (In Figures) | Bidder's Rate (In words) | Amount | Remarks |
|----|---|------|----------|----------------------------|--------------------------|--------|---------|
| A | Civil Works | | | | | | |
| 1 | Earth work in excavation of foundation of structures, including construction of shoring and bracing, removal of stumps and other deleterious matter and backfilling with approved Material as per Drawing and Technical Specifications.(By | m3 | 3.47 | | | | |
| 2 | Providing mechanically woven double twisted crates / mattress (Heavy zinc coated Hexagonal mesh type 100 mm x 120 mm, mesh wire 3 mm, selvage wire 3.9 mm, lacing wire 2.4 mm) including rolling, cutting and with lacing wire and binding wire as per specification. | m2 | 110.00 | | | | |
| 3 | Providing and filling stone/boulder in gabion boxes/mattress etc.. Including dressing, bedding, bonding all complete as per Drawing and Technical Specifications. | m3 | 19.40 | | | | |
| | Estimated Cost | | | | | | |
| | Vat (13%) | | | | | | |
| | Sub total withVAT | | | | | | |

Name of Contractor:-

Address:-

Date:-


Seal:-



कोष बहादुर नेपाली
कोष प्रशासक/अधिकारी

Dangisharan Rural Municipality
Office of the Rural Municipality Executive
Dangisharan-03, Dang
Lumbini Province, Nepal
Bill of Quantity




कर्ण बहादुर नेपाल
मुख्य प्रशासकीय अधिकारी
 Amount

| SN | Description Of Work | Units | Quantity | In fig | In word | Remarks |
|----|--|-------|----------|--------|---------|---------|
| 1 | Roadway excavation in all types of soil as per Drawing and Technical Specification including removal of stumps and other deleterious matter; all lift and leads as per Drawing and Instruction of the Engineer. (Mechanical Means) | Cum. | 3262.13 | | | |
| 2 | Earthwork in excavation of foundation of structure in ordinary soil including construction of shoring and bracing, removal of stumps and other deleterious matter and backfilling with approved material as drawings and technical specifications @ Depth upto 3m (mechanical means) | Cum. | 37.00 | | | |
| 3 | Transportation of excavated materials all Complete works | Cum. | 3262.13 | | | |
| 4 | Providing and laying granular local mix gravel on prepared road surface by mechanical means all complete. | Cum. | 51.80 | | | |
| 5 | Providing & laying boulder stone soling in foundation & floor including voids filling with sand all complete as per instruction of the site engineer. | Cum | 0.40 | | | |
| 6 | Providing, laying, compacting and curing plain cement concrete M10 (1:3:6) in foundation with cement, sand and stone ballast 20mm gauge finishing to approved level, lines and dimensions all complete as per drawings, specifications and instruction of the site engineer. | Cum | 0.32 | | | |
| 7 | Providing and laying Plum Concrete mixing of 60% M15 concrete and 40% boulder/stones (Boulder mixed concrete) including pipes for weep holes etc all complete as per Drawing and Technical Specifications. (Mechanical Means) | Cum | 52.05 | | | |
| 8 | Providing mechanically woven double twisted crates / mattress (Heavy zinc coated Hexagonal mesh type 100 mm x 120 mm, mesh wire 3 mm, selVage wire 3.9 mm, lacing wire 2.4 mm) including rolling, cutting and with lacing wire and binding wire as per specification. | sqm | 22.00 | | | |
| 9 | Providing and filling stone/boulder in gabion boxes/mattress etc.. Including dressing, bedding, bonding all complete as per Drawing and Technical Specifications. | Cum | 4.00 | | | |

| | | | | | | |
|--|--|-----|-------|--|--|--|
| 10 | Providing, laying, compacting and curing plain cement concrete M15 (1:2:4) in Solid Floor with cement, sand and stone ballast 20mm gauge finishing to approved level, lines and dimensions all complete as per drawings, specifications and instruction of the site engineer. | Cum | 3.75 | | | |
| 11 | Reinforcement bars (Grade 415 or above) work including straightening, cleaning, cutting, bending, binding with 20 SWG annealed wire & fixing in position as per drawing, bar bending schedule for raft foundation column, beam, wall, slab in all R C C works as per specification, drawing & instruction of site engineer. Approved brands: Hinnal Iron, Panhalkanya or equivalent. | Kg | 93.20 | | | |
| 12 | Providing, Preparing and Installing form work including necessary supports and removing after completion for Foundation and footings. (Class F1 Finish). | Sqm | 91.72 | | | |
| Total Amount (NRs.) VAT@ 13 % (NRs.) Grand Total (NRs.) | | | | | | |

Firm name :-
Authorize sign :-
Firm seal :-
Date :-